

## **ADDENDUM #1**

**All clauses set forth in the Bidding Documents, Contract Documents and General Requirements of the original Contract Documents shall apply to and govern this work. The addendum refers to changes and additions to the original Contract Documents and is to be read in conjunction with the same. All other parts of the original Contract Documents are to be considered as applying to the work of this Contract with the exceptions and changes as noted below.**

### **CLARIFICATIONS**

1. General Contractor shall coordinate the respective Safeswap footing details for each play feature. Refer to Appendices for play feature construction details.
2. General Contractor shall carry the costs associated with locating underground wiring and other services.

### **SCHEDULES**

1. Reference Hardware Schedule:
  - .1 Add new Hardware Schedule (1 page), issued with and forming part of this addendum.

### **SPECIFICATIONS**

1. Appendices:
  - .1 Clarification: Items noted to be "BY INSTALLER" are to be read as "BY GENERAL CONTRACTOR" for the purpose of this contract.

### **DRAWINGS**

1. Reference Drawing C1 – Site Plan, Sections, Elevations, Details, & Notes:
  - .1 Reference Detail SP – Site Plan:
    - .1 Clarification: Existing culvert is a 450mm diameter HDPE Solflo culvert.
    - .2 Delete "64mm $\phi$  MUNICIPEX OR COPPER TYPE K WATER SUPPLY" and replace with "76mm $\phi$  SDR26 PVC WATER SUPPLY"
    - .3 Clarification: New Gate Valve to be sized for a 76mm water line.
  - .2 Reference Detail 2 – Plan: New Utility Building:
    - .1 Clarification: New 76mm water line to be reduced and tied into owner supplied 51mm water meter inside the building.
    - .2 Clarification: Drain line from pit to be 102mm diameter PVC storm pipe.
    - .3 Add new note: "FLOOR DRAIN STANDARD OF ACCEPTANCE: ZURN, MIFAB, SCHLUTER. C/W TRAP PRIMER CONNECTION."
2. Reference Drawing M1 – Plumbing and Electrical Plan, Details & Notes:
  - .1 Reference Electrical Notes:
    - .1 Add new note number 3, "Interior surface mounted conduit shall be PVC in Town Hall Electrical room and new Utility Building."
    - .2 Add new note number 4, "Supply and install mounting hardware required to install new circuit breaker in 'EP1' panel."

END OF SECTION

**SET #HW01**

Door:

3 Hinges	TA314 4½ x 4 NRP	26D
1 Closer	1431 CPS	EN
1 Latchset	21-8204 LNP MK, VK	26D
1 Deadbolt	63-485	26D
1 Weather stripping	W-49 x 17	MF
1 Threshold	CT-10 x 914	CA
1 Door Sweep	W24S x 914	CA