



Building and Planning Division  
Transportation, Infrastructure and Energy

Tel 902 368 5060  
Fax1 902 368 5395  
Fax2 902 569 0590  
[www.gov.pe.ca/](http://www.gov.pe.ca/)

PO Box 2000  
Charlottetown  
Prince Edward Island  
Canada C1A 7N8

# Addendum

efficiencyPEI Interior Fit-up  
United Plaza  
2352-17089

**ADDENDUM # 1**

**Date : August 21, 2018**

**Page 1 of 1**

The following amendment to the tender documents is effective immediately. This addendum shall form part of the contract documents.

**Note: Please indicate this addendum number on the Contract Tender Form.**

Item

Description

**A-1-1**

**Refer to Drawing A4 - Architectural Standards**

Item 2.2 Ceilings:

Please note, the Landlord will be removing all ceiling tiles within the area of work due to them possibly containing Hazardous Materials. Contractor will be responsible for supply and install of new ceiling tiles within area of work.

**A-1-2**

**Refer to Drawing A4 - Architectural Standards**

Item 2.6 Electrical:

Clarification note .8 - Contractor to supply and install four (4) junction boxes above ceiling for future use in room 109. Each junction box shall have two (2) circuits and two (2) cat 6 data lines. Lines to be terminated at both ends. Contractor responsible to test these lines prior to completion.

Add note .9 - Electrical contractor responsible for installation of weather head from new data rack to roof for the wireless internet access.

Add note .10 - Electrical contractor responsible for supply and install of pack pole required in room 102.

Add note .11 - Existing light switches being reused to be switched out to new dimmable switches for new LED flat panel lights.

**- END OF ADDENDUM -**