

---

The following amendment to the tender documents is effective immediately. This addendum shall form part of the contract documents.

---

Item Description

**SPECIFICATIONS:**

A8.1 Ref: Section 23 05 00 Common Work Results for HVAC:

- .1 Add the following as 3.4 Hydronic Tie-in:
  - "3.4 Hydronic Tie-in:
    - .1 Due to the current schedule for the project, the new heaters and modifications to the existing heaters will be done during the heating season.
    - .2 For all tie-ins to the existing system, the contractor shall allow for freezing of the branch lines serving the heaters to be modified. The locations of the branch lines are approximately shown on the drawings in the ceiling of the 1<sup>st</sup> floor spaces. Note that these branch lines also serve heaters on the floor above; the contractor shall provide electric temporary heat on the affected rooms above until the heating has been restored.
    - .3 The contractor may temporarily isolate the piping in the wing to aid with the freezing of the piping. Any shut-down shall be between Friday 4pm to Monday 8am. The contractor shall make every effort to make the shut-down as short as possible. Valves are to be installed and piping reconnected to the heaters for the floor above and service restored immediately. The contractor is responsible for maintaining all rooms to a minimum of 15°C while unoccupied and 21°C while occupied.
    - .4 Contractor shall ensure system is refilled after tie-in is completed and new heater is active. Contractor shall bleed all affected heaters on the second floor immediately after reconnection and after new heater is filled.
    - .5 Coordinate timing of the tie-ins with the Owner. The tie-ins are expected to be completed before any other work is performed."

**DRAWINGS:**

A8.2 Ref: Drawing M101:

- .1 Delete note referring to isolation and draining. Replace with the following:  
"Refer to specifications 23 05 00 3.4 for additional details."

**END OF SECTION**