



Building and Planning Division
Transportation, Infrastructure and Energy

PO Box 2000
Charlottetown
Prince Edward Island
Canada C1A 7N8

Tel 902 368 5060
Fax1 902 368 5395
Fax2 902 569 0590
www.gov.pe.ca/

Addendum

Access Summerside Interior Renovations 2060-19020

ADDENDUM #002

Date : December 16, 2019

Page 1 of 1

The following amendment to the tender documents is effective immediately. This addendum shall form part of the contract documents.

Note: Please indicate this addendum number on the Contract Tender Form.

Item

Description

A-2-1

Refer to Specification Section "A" Invitation to Bidders:

Add to Scope of Work: Item 7 Asbestos Abatement:

- .1 General Contractor responsible to hire Abatement Contractor to remove approx. fifty (50) asbestos containing pipe insulation elbows located in the plumbing chases and above ceiling. All work done in accordance with the PEI Occupational Health and Safety Act.
- .2 Abatement Contractor to submit and obtain approval from PEI WCB/OHS Division for the procedure to be followed during the completion of the asbestos abatement work. A copy of the signed Asbestos Notification Permit is to be submitted to TIE, attention Jonathan Gauthier (jwgauthier@gov.pe.ca) prior to the start of the contract work.
- .3 All abatement work to be completed after normal working hours or on weekends.
- .4 Abatement Contractor responsible to hire an independent air testing agency to monitor and provide an approved air quality testing report to insure work space is safe to continue working.
- .5 Abatement contractor to be conscious of cleanliness and coordinate abatement schedule with TIE Representative.

A-2-1

Refer to Detail 2/A2 :

- .1 Contractor to remove existing cast iron mop basin located in Electrical room on the main floor. Contractor responsible to modify existing piping for connection for new floor mounted mop basin. Standard of acceptance Fiat Model - MSB2424, include a combination dome strainer & lint basket; service faucet (830-AA); hose and hose bracket (832-AA); mop hanger (889-CC) or approved equal.
- .2 Contractor to install FRP panel behind new mop service basin to 1200mm (48") AFF c/w trims and silicone sealed.

- END OF ADDENDUM -