

PROJECT Westwood Primary School Humidification Upgrades TIE Project No. 690-20005	PROJECT NO. 20-108
DESCRIPTION Addendum No. 1	DATE June 2, 2020

Item No. 1 Reference Specification – Section A-Invitation to Bidders Tender

- .1 Clarification – Submission Time:
 Tender submissions will be received in clearly marked, sealed envelopes in the tender box provided at the Security Desk at the main entrance of the Jones Building, 11 Kent Street, Charlottetown, PE C1A 7N8 between 11:00 AM and 2:00 PM, Local Time, on the tender closing date. Tender closes at 2:00 PM.

Item No. 2 Reference Drawing M-1

- .1 Clarification – Detail 3: HRV-1 condensate insulation:
 Provide new insulation and jacketing on existing 19mm condensate piping serving HRV-1 humidification distribution manifold, from tie-in to main to the tee at manifold connection.
- .2 Clarification – Detail 4: Humidifier locations:
 Humidifier HUM-1 shall be moved in project south direction towards existing AHU-3 and Humidifier HUM-2 shall be moved in project north direction towards existing 1200x400 duct to maintain suitable walking path between the two systems.

Item No. 3 Reference Drawing M-3

- .1 Clarification – Par. 5.2.2:
 Memco Controls Ltd. Is the acceptable automatic controls contractor.