



Transportation, Infrastructure,  
and Energy

64 Park Street  
Charlottetown  
Prince Edward Island  
Canada C1A 5G7

Tel 902 368 5090  
Fax 902 368 6244  
[www.gov.pe.ca/](http://www.gov.pe.ca/)

**ADDENDUM NUMBER 1**  
for  
**Rte 10 – Augustine Cove (Central Coastal Dr) 2020**  
(Page 1 of 1)

---

**TO: All Bidders**  
**FROM: Stephen Szwarc, P.Eng.**  
**Director, Highway Maintenance**  
**DATE: July 23, 2020**  
**SUBJECT: Revisions**

---

1. In **SCHEDULE A – SPECIAL PROVISIONS** under **SECTION 603 – HOT MIX ASPHALTIC CONCRETE (Item 60350 – Asphalt Seal: B)** remove:  
A \$4.00/tonne deduction off the tendered price of Asphalt Seal shall be made should the contractor choose to use up to 15% RAP. Should the contractor choose to use less than 15% RAP a proportional deduction shall be made.

And add:

Asphalt Seal: C meeting the requirements in Section 603 may be used in place of Asphalt Seal: B. No additional compensation shall be provided for the use of one material over the other.

The RAP shall be of high quality, have a minimum asphalt content of 5.0% and meet the asphalt concrete gradation requirements in Section 603, Table 603-4 or be approved by the Engineer.

2. In **SCHEDULE A – SPECIAL PROVISIONS** add:  
**SECTION 500 – ASPHALT CEMENT**  
**(Item 50101 – Asphalt Cement)**  
Should the contractor choose to use RAP in the production of the hot mix asphaltic concrete surface B mix the asphalt cement shall be paid for by the metered asphalt cement in the mix (virgin binder and binder contribution from the RAP).

**A signed copy of this addendum must be included with your bid submission on this project.**

---

Signature of Contractor