

ADDENDUM #2

All clauses set forth in the Bidding Documents, Contract Documents and General Requirements of the original Contract Documents shall apply to and govern this work. The addendum refers to changes and additions to the original Contract Documents and is to be read in conjunction with the same. All other parts of the original Contract Documents are to be considered as applying to the work of this Contract with the exceptions and changes as noted below.

DRAWINGS

1. Reference Drawing M1 - Demolition & Installation, Mechanical Plans & Schematics:
 - .1 Reference Detail 2:
 - .1 Add following Note:
"Replace existing motorized damper and ductwork with new motorized damper and ductwork. Damper/ductwork dimensions are approximately 24 inches high x 24 inches wide. Contractor to extend ductwork from existing location down to location 24 inches above the finished floor."
2. Reference New Sketches:
 - .1 See sketches SK-6, SK-7, SK-8, SK-9 and SK-10, attached to and forming part of this addendum, for associated electrical work.

END OF SECTION

ELECTRICAL SPECIFICATION

I. GENERAL CONDITIONS

- A) TENDER REQUIREMENTS, THE PROJECT CONTRACT, RELATED DOCUMENTATION AND GENERAL REQUIREMENTS GOVERN THE WORK OF THIS CONTRACT/TRADE.
- B) ALL ELECTRICAL WORK IS TO BE CARRIED OUT BY QUALIFIED, LICENSED ELECTRICIANS OR APPRENTICES FOR THE PROVINCE OF PRINCE EDWARD ISLAND AND THE ELECTRICAL CONTRACTOR MUST HAVE A VALID CONTRACTOR LICENSE ISSUED BY THE PROVINCE OF PRINCE EDWARD ISLAND.
- C) ELECTRICAL CONTRACTOR TO FURNISH ALL LABOUR, MATERIALS, TOOLS AND EQUIPMENT REQUIRED TO COMPLETE ALL WORK SHOWN ON THE DRAWINGS AND HEREIN SPECIFIED. THE WORK IS TO BE IN ACCORDANCE WITH RULES AND REGULATIONS OF ALL AUTHORITIES HAVING LEGAL JURISDICTION OVER THE WORK. PROVIDE ANY SMALL ITEMS OF WORK NOT SPECIFICALLY CALLED FOR BUT REQUIRED TO COMPLETE THE INTENDED INSTALLATION.

2. CODES, PERMITS AND INSPECTION

ALL WORK IS TO BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CANADIAN ELECTRICAL CODE (CEC), THE NATIONAL BUILDING CODE (NBC), AND THE NATIONAL FIRE CODE (NFC).

3. REMOVALS AND ALTERATIONS

- A) WORK OF THIS SECTION CONSISTS OF THE COMPLETE REMOVAL OF ALL OBSOLETE OR ABANDONED ELECTRICAL EQUIPMENT AND MATERIALS AS INDICATED ON THE DRAWINGS, AND THE ALTERATIONS OF EXISTING ELECTRICAL SERVICES AFFECTED BY THE RENOVATIONS.
- B) ANY EXISTING CONDUIT, WIRING, BOXES OR EQUIPMENT THAT IS TO REMAIN IN SERVICE IS TO BE PROPERLY SUPPORTED AS REQUIRED BY THE CEC. ANY ADDITIONAL HANGERS, STRAPS OR FASTENERS THAT ARE REQUIRED ARE TO BE SUPPLIED AND INSTALLED UNDER THIS CONTRACT.
- C) ANY EXISTING ELECTRICAL CIRCUITS AND/OR EQUIPMENT THAT ARE INTERRUPTED DURING CONSTRUCTION TO ACCOMMODATE ALTERATIONS BUT ARE TO REMAIN IN SERVICE ARE TO BE RECONNECTED AND CIRCUITS MADE GOOD.
- D) THE OWNER INTENDS TO CARRY OUT DAY-TO-DAY BUSINESS AS USUAL THROUGHOUT THE FACILITY DURING THE RENOVATION. ALL POTENTIALLY DISRUPTIVE WORK INCLUDING POWER OUTAGES ARE TO BE COORDINATED AND SCHEDULED WITH THE OWNER IN AN EFFORT TO MINIMIZE DISRUPTION.

4. IDENTIFICATION

- A) PROVIDE AND INSTALL LAMICOID IDENTIFICATION NAMEPLATES ON ALL EQUIPMENT, DISCONNECT SWITCHES, PANELBOARD, STARTERS ETC. INDICATING THE LOAD SERVED, SYSTEM AMPERAGE, VOLTAGE, PHASING AND CIRCUIT NUMBER WHERE APPLICABLE.
- B) LAMICOID NAMEPLATES ARE TO BE MINIMUM 3/4"x3" WITH 1/4" LETTERS AND WHITE WITH BLACK ENGRAVED LETTERS AND ARE TO BE INSTALLED WITH CONTACT CEMENT TO EQUIPMENT ENCLOSURES.
- C) EACH BRANCH PANELBOARD IS TO HAVE A TYPEWRITTEN BREAKER DIRECTORY INDICATING THE LOAD CONNECTED TO EACH CIRCUIT. DIRECTORIES ARE TO BE MOUNTED ON THE INSIDE OF THE PANELBOARD DOOR WITH A TRANSPARENT PLASTIC COVER. EXISTING BREAKER DIRECTORIES WHICH ARE MODIFIED BY RENOVATIONS ARE TO BE UPDATED.
- D) ALL JUNCTION/PULL BOXES ARE TO BE MARKED WITH AN INDELIBLE INK MARKER TO IDENTIFY THE CIRCUIT NUMBER OF ENCLOSED WIRING AND THE PANEL NAME.

5. COORDINATION

BE RESPONSIBLE FOR COORDINATING THE INSTALLATION OF EQUIPMENT, CONDUIT AND CABLE WORK, LIGHTING FIXTURES, ETC. WITH OTHER TRADES PRIOR TO THE ACTUAL INSTALLATION.

6. WARRANTY

WARRANT ALL WORK AND MATERIALS INSTALLED UNDER THIS CONTRACT, AGAINST ALL DEFECTS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR AFTER ACCEPTANCE OF SAME BY OTHERS.

7. CONDUIT AND FITTINGS

- A) EMT COMPLETE WITH STEEL SET SCREW COUPLINGS AND CONNECTORS TO BE USED FOR ALL INTERIOR BRANCH CIRCUIT WORK UNLESS OTHERWISE INDICATED. INSTALL A SEPARATE BOND WIRE SIZED IN ACCORDANCE WITH CEC REQUIREMENTS IN ALL CONDUITS.
- B) WHERE CONDUIT PENETRATES THROUGH FIRE RATED STRUCTURES, FIREPROOFING AND SMOKE SEALING IS TO BE PACKED AROUND CONDUIT TO MAINTAIN FIRE RATING OF STRUCTURE WHICH IT PASSES THROUGH. ACCEPTABLE MATERIAL: 3M BRAND FIRE BARRIER CAULK CP 25 OR 303 PUTTY COMPOUND OR APPROVED EQUAL. PROVIDE FIRE COLLARS IN ADDITION TO FIRE CAULKING WHERE REQUIRED.
- C) CONDUIT AND CABLES ARE TO BE SUPPORTED INDEPENDENTLY OF OTHER EQUIPMENT USING ONE-HOLE STEEL STRAPS FOR UNDER 2"C, TWO-HOLE STEEL STRAPS FOR 2"C AND LARGER, AND BEAM CLAMPS, AND SPRING STEEL FASTENERS IN ACCORDANCE WITH THE CEC.
- D) PROVIDE LOW VOC MASTIC COMPOUND WEATHERPROOF SEAL WHERE CONDUITS PASS THROUGH EXTERIOR WALLS OR STRUCTURES.

8. WIRE AND CABLE

- A) ALL WIRES TO BE COPPER RW90, RATED 600V, INSTALLED IN CONDUIT UNLESS OTHERWISE INDICATED. FLEXIBLE METAL CONDUIT IS AN ACCEPTABLE ALTERNATE TO CONDUIT FOR INTERIOR BRANCH CIRCUITS CONCEALED IN STUD WALL CONSTRUCTION.
- B) TECK CABLE RATED FOR 600V WITH FT4 JACKET TO BE USED FOR FINAL CONNECTIONS TO MECHANICAL EQUIPMENT AND WHERE INDICATED. TERMINATE WITH SPIN-ON STYLE CONNECTORS. ACCEPTABLE MATERIAL: T & B STAR-TECK.

9. CONNECTORS FOR WIRES

USE GEL FILLED TWIST-ON CONNECTORS IN DAMP OR WET LOCATIONS. ACCEPTABLE MATERIAL: KING INNOVATION DRY CONN.

10. GROUNDING AND BONDING

- A) ENTIRE ELECTRICAL SYSTEM TO BE GROUNDED AND BONDED IN ACCORDANCE WITH THE REQUIREMENTS OF THE CEC AND LOCAL AUTHORITIES.

II. POWER DISTRIBUTION SYSTEM

A) DISCONNECT SWITCHES.

- a) HEAVY DUTY TYPE WITH RATING INDICATED ON THE DRAWINGS, FUSIBLE WHERE INDICATED, QUICK-MAKE, QUICK-BREAK, AVOIDABLE COVER INTERLOCK, LOCKABLE IN "OFF" POSITION. PROVIDE AUXILIARY CONTACTS IN DISCONNECT SWITCHES CONNECTED DIRECTLY TO VFD'S.
- b) CSA TYPE 4x ENCLOSURE WHERE INDICATED OR WHERE WEATHERPROOF SWITCHES ARE REQUIRED, OTHERWISE PROVIDE CSA TYPE I.

B) PANELBOARDS

- a) PANELBOARDS TO BE OF THE AMPERAGE, VOLTAGE AND PHASING INDICATED ON THE PANEL SCHEDULE, COMPLETE WITH CIRCUIT BREAKERS AS INDICATED.
- b) PANELBOARDS TO BE SURFACE MOUNTED COMPLETE WITH HINGED DOOR, LATCH, LOCK AND DIRECTORY, BAKED GREY ENAMEL FINISH.
- c) CIRCUIT BREAKERS TO HAVE THERMAL MAGNETIC TRIP PROTECTION WITH BIMETALLIC ELEMENTS FOR DELAY OVERLOAD PROTECTION. TWO AND THREE POLE BREAKERS TO HAVE INTERNAL COMMON TRIP. BREAKERS ARE TO BE 10 KAIC AT 208V, OR TO MATCH FAULT INTERRUPTING CAPACITY OF EXISTING PANELBOARD IN WHICH THEY ARE INSTALLED. PROVIDE ALL MOUNTING HARDWARE AS REQUIRED FOR INSTALLING NEW BREAKERS IN EXISTING PANELS.
- d) CIRCUIT BREAKERS TO BE BY THE SAME MANUFACTURER AS THE PANELBOARD IN WHICH THEY ARE BEING INSTALLED. BREAKERS MUST BE NEW, COMPLETE WITH ORIGINAL FACTORY WARRANTY AND SUPPLIED FROM AN AUTHORIZED MANUFACTURER'S DISTRIBUTOR.

C) FULL VOLTAGE COMBINATION MAGNETIC STARTERS

- a) COMBINATION MAGNETIC STARTERS OF SIZE, TYPE, RATING AND ENCLOSURE TYPE C/W COMPONENTS AS INDICATED.
- b) CONTACTOR SOLENOID OPERATED, RAPID ACTION TYPE.
- c) BIMETAL MOTOR OVERLOAD PROTECTIVE DEVICE.
- d) POWER AND CONTROL TERMINALS.
- e) WIRING AND SCHEMATIC DIAGRAM INSIDE STARTER ENCLOSURE IN VISIBLE LOCATION.
- f) NUMBER MARKING IDENTICAL TO DIAGRAM.
- g) CIRCUIT BREAKER DISCONNECT WITH OPERATING LEVER ON OUTSIDE OF ENCLOSURE AND CAPABLE OF BEING LOCKED IN "OFF" POSITION WITH UP TO 3 PADLOCKS.
- h) PUSHBUTTONS/HAND-OFF-AUTO SELECTOR SWITCHES: HEAVY DUTY, LABELED AS HAND-OFF-AUTO.
- i) TWO 120VAC PILOT LIGHTS: "RUN" TO BE RED. "OFF" TO GREEN AND I-N/O AND I-N/C SPARE AUXILIARY CONTACTS.
- j) SINGLE PHASE, DRY TYPE, 50 VA CONTROL TRANSFORMER WITH PRIMARY VOLTAGE AS INDICATED AND 120V SECONDARY, COMPLETE WITH PRIMARY AND SECONDARY FUSES, INSTALLED WITH STARTER AS INDICATED.
- k) ENCLOSURE: CSA TYPE I UNLESS INDICATED OTHERWISE.
- l) ACCEPTABLE MATERIAL: SIEMENS #V2ABI7C1K2RKG1364 (3HP), SCHNEIDER #LEI SERIES, CULTER-HAMMER #XT SERIES, ALLEN-BRADLEY BULLETIN #112.

LEGEND	
	UNDERGROUND WIRING
	SURFACE MOUNTED WIRING
A-10	INDICATES CIRCUIT #10 IN PANEL 'A'
GENERAL SUB SCRIPTS	
4x -	INDICATES CSA 4x ENCLOSURE
X -	INDICATES EQUIPMENT TO BE REMOVED
	'MI' ELECTRICAL PANEL, SURFACE MOUNTED 'MI' - INDICATES PANEL DESIGNATION
	SINGLE PHASE MOTOR
	UNFUSED DISCONNECT SWITCH XX - INDICATES SWITCH RATING
	DIRECT CONNECTION
	EXISTING MANUAL MOTOR SWITCH
	COMBINATION MAGNETIC MOTOR STARTER



CLIENT
PEI Department of
Transportation
Infrastructure & Energy

PROJECT TITLE
Georgetown School
Boiler Replacement
Oil Option

SHEET TITLE
Electrical
Specification
& Legend

Charlottetown, P.E.I., Canada, C1A 7L3 Phone (902) 368-2300 Fax (902) 566-3768 www.colesassociates.com


REVISIONS:

DATE: Sept. 2018

DRAWN BY: M.E.M., C.E.T.

PROJECT NUMBER:

DRAWING NUMBER:
181086A SK-6



- NOTES:**
1. TRACE OUT, DISCONNECT, AND REMOVE ALL EXISTING ELECTRICAL ASSOCIATED WITH THE BOILER AND ASSOCIATED CIRCULATION PUMPS.
 2. EXISTING BOILER REMOTE SWITCH TO BE TRACED OUT, DISCONNECTED AND REMOVED.
 3. EXISTING PANELBOARD AND ASSOCIATED FEEDERS TO BE DISCONNECTED AND REMOVED AND BRANCH CIRCUIT FOR EXISTING WASHING MACHINE AND DRYER TO BE NEATLY COILED AND CAPPED FOR FUTURE EXTENSION TO NEW PANELBOARD.



DEMOLITION FLOOR PLAN - OIL OPTION
1:25

CLIENT
PEI Department of Transportation Infrastructure & Energy

PROJECT TITLE
Georgetown School Boiler Replacement Oil Option

SHEET TITLE
Electrical Demolition


DATE: Sept. 2018
DRAWN BY: M.E.M., C.E.T.

REVISIONS:


PROJECT NUMBER: 181086A
DRAWING NUMBER: SK-7

Charlottetown, P.E.I., Canada, C1A 7L3 Phone (902) 368-2300 Fax (902) 566-3768 www.colesassociates.com

Coles Associates
architecture, engineering, project management



- NOTES:**
1. REMOTE EMERGENCY STOP SWITCHES FOR NEW BOILERS TO BE LOCATED AT 1400mm AFF. COORDINATE EXACT LOCATION OF SWITCHES ON SITE.
 2. EXISTING BRANCH CIRCUIT TO BE REROUTED AND EXTENDED AS NEEDED TO CONNECT DRYERS TO NEW PANELBOARD.
 3. CONNECT NEW PANELBOARD WITH 3#3, #6 BOND IN 53mmC TO EXISTING SPLITTER TROUGH.
 4. INSTALL 30A, 240V UNFUSED TO DISCONNECT ADJACENT TO VFD FOR HEATING PUMPS 'P-3' AND 'P-4'. COORDINATE EXACT LOCATION OF DISCONNECT SWITCH ON SITE. DISCONNECT SWITCH TO BE C/W ONE (1) NORMALLY OPEN CONTACT WHICH IS CONNECTED TO THE VFD TO SIGNAL REMOTE SHUTDOWN.
 5. INSTALL 2#12, #14 BOND IN 3/4"C BETWEEN EACH 120V ANTI-SIPHON VALVE TO THE ASSOCIATED BOILER CONTROL PANEL. COORDINATE CONNECTION AND EXACT TERMINATION WITH BOILER CONTRACTOR.



www.colesassociates.com

REVISIONS:

DATE: Sept. 2018

DRAWN BY: M.E.M., C.E.T.

PROJECT NUMBER: 181086A SK-8

PHONE (902) 368-2300

FAX (902) 566-3768

Charlottetown, P.E.I., Canada, C1A 7L3

SHEET TITLE: **Electrical Floor Plan**


PROJECT TITLE: **Georgetown School Boiler Replacement Oil**

CLIENT: **PEI Department of Transportation Infrastructure & Energy**

Coles Associates
 architecture, engineering, project management

PANEL 'MI'													
DESIGNATION	LOAD		P	BKR	CIRCUIT			BKR	P	LOAD		DESIGNATION	
	A	B								A	B		
DRYER	2800		2	30	1	A	2	15	1	1000		BOILER 'B-1'	
		2800			3	B	4	15	1		1000	BOILER 'B-2'	
WASHING MACHINE	700		1	15	5	A	6	15	1	500		PUMP 'P-3'	
SPARE		-	1	15	7	B	8	15	1		500	PUMP 'P-4'	
SPARE	-		1	15	9	A	10	20	2	1250		PUMP 'P-1'	
SPARE		-	1	15	11	B	12				1250		
SPACE	-				13	A	14	20	2	1250		PUMP 'P-2'	
SPACE		-			15	B	16				1250		
SPACE	-				17	A	18	15	1	-		SPARE	
SPACE		-			19	B	20	15	1		-	SPARE	
SPACE	-				21	A	22	15	1	-		SPARE	
SPACE		-			23	B	24	15	1		-	SPARE	
SPACE	-				25	A	26	15	1	-		SPARE	
SPACE		-			27	B	28	15	1		-	SPARE	
SPACE					29	A	30	15	1	-		SPARE	
PHASE LOADS:	3500	2800							4000	4000			
TOTAL PHASE LOADS:	7500	6800							SUPPLY: 120/240V, 1Ø, 3w				
TOTAL LOADS:	14300							MAINS: 100A, MB, TOP FED					
								NUMBER OF CIRCUITS: 30					
CURRENT AT 240V/IPH:	60							MOUNTING: SURFACE					






DETAIL NOTES:

1. B = BRANCH CIRCUIT CONDUIT. QUANTITY AND SIZE AS INDICATED.
2. BACKFILLING OF TRENCH IN LAYERS NOT EXCEEDING 12" (MECHANICALLY TAMPED).
3. USE NEW SOIL FREE FROM LARGE ROCKS OR DEBRIS FOR BACKFILL.
4. IF SITE CONDITIONS PROHIBIT TRENCH AS PER THIS DRAWING, ADVISE CONSULTANT.
5. 1/4" DIA. NYLON ROPE INSTALLED IN ALL DUCTS.
6. ALL CONDUITS ARE TO BE LABELED WITH WEATHER PROOF TAGS INDICATING THE DESTINATION OF THE CONDUITS.

 BRANCH CIRCUIT CONDUIT

 TRENCH DETAIL
SK-8 SK-10 NTS



DETAIL NOTES:

1. 120V SWITCHING OUTPUT FROM BOILER CONTROLLER TO BE WIRED TO CONTACTOR BY ELECTRICAL CONTRACTOR. COORDINATE CONNECTION AND EXACT TERMINATION POINT WITH BOILER CONTRACTOR.
2. DEVICE TO BE FRONT COVER MOUNTED.

 COMBINATION MAGNETIC MOTOR STARTER FOR PUMPS 'P-1' & 'P-2'
SK-10 SK-10 NTS



Charlottetown, P.E.I., Canada, C1A 7L3 Phone (902) 368-2300 Fax (902) 566-3768 www.colesassociates.com

REVISIONS:
DATE: Sept. 2018
DRAWN BY: M.E.M., C.E.T.
PROJECT NUMBER:
DRAWING NUMBER: 181086A SK-10

SHEET TITLE
Trench Detail
& Schematic
PROJECT TITLE
Georgetown School
Boiler Replacement
Oil Option

Coles Associates
architecture, engineering, project management

CLIENT
PEI Department of
Transportation
Infrastructure & Energy