



Addendum #2

Dec. 4, 2018

SITE PREPARATION P.E.I.
Summers Side Seniors Complex

Transportation, Infrastructure and Energy
Project # 4582-18022

The following amendment to the tender documents is effective immediately. This addendum shall form part of the contract documents.

Note: Please ensure this addendum number is noted in the final bid.

Item	Description
1.	Table of contents add "01 78 15 Closeout Documentation.
2.	Reference Section 00 21 10 Instructions to Bidders <ul style="list-style-type: none">a. Para 1.2 Scope of Work add: 7. Provide and connect Storm water lines as shown on C1 and C2 drawings.
3.	Reference Section 00 31 30 Subsurface Investigation Report – Please find included with this addendum a copy for information.
4.	Reference Section 01 50 00 Temporary Requirements – Project signage to be coordinated by Owner. Delete para 1.13 Project Signage.
5.	Reference Section 01 57 13 Temporary Erosion and Sediment Control – Add para 3.4 Environmental management. <p style="margin-left: 40px;">3.4 Environmental Management to be completed in accordance with EMS Approval to proceed No. PT18-030 terms and conditions. A copy is included with and forms part of this addendum. This document references TEI EPP document that can be found at the following link:</p> <p style="margin-left: 40px;">https://www.princeedwardisland.ca/sites/default/files/publications/envprotectplan.pdf</p>
6.	Reference Section 01 35 10 - Safety Requirements – Para 17 Safety Officer - Clarification: It is intended that the Safety officer have the minimum qualifications listed, be present on site as stated, and the Contractor prior to beginning the work must notify the Owner if this individual will also be assigned other duties on site.
7.	Reference Section 31 22 10 Rough Grading



COAST
DESIGN
INC.

Box 21142
Charlottetown PE
C1A 9H6

david@coastdesign.ca
902-626-8253

- a. Clarification: Approximately 220 m³ of topsoil is to be retained and stockpiled on site. The remainder/excess topsoil is to be removed and disposed of from site by the Contractor.
- 8. Drawings C1 & C2:**
- a. Clarification General Contractor is to remove all soil down to Till and reinstate grades as shown on drawings with select borrow. This may require select borrow in some areas to be in excess of those noted in the details on page C2. Refer also to geo-technical report for additional information.
 - b. Clarification Roadway access – Contractor to provide Class A gravel ramp providing access from paved road to grade of select borrow on new driveway.

End of Addendum