



Department of Transportation, Infrastructure & Energy
PO Box 2000
Charlottetown
Prince Edward Island
Canada C1A 7N8 Tel: 902 368 5180

**CAPITAL PROJECTS
ADDENDUM NUMBER 3
for
NORTH LAKE BRIDGE - STRUCTURE REPLACEMENT
(Scheduled Tender Closing 23 July 2019)**

TO: All Bidders

FROM: Neil Lawless, P.Eng.
Bridge Engineer

DATE: 22 July 2019

SUBJECT: Errata to Schedule 'A'
Errata to Drawings

1. Schedule A: Bid Item #60350 - Asphalt Seal B:

Insert the following paragraph:

The unit price for this item shall also include all costs associated to router 40mm wide x 40mm deep and fill with hot applied low modulus expansion joint across full road width at three (3) locations at each approach. Locations: approach slab meets bridge deck, approach slab meets sleeper slab, and where asphalt on grade meets sleeper slab.

2. Schedule A: Bid Item Bid Item #110117 - Approach Slab Concrete:

Insert the following paragraph:

The unit price for this item shall also include all costs associated to supply and place 2 sheets of 6mil poly below both approach slabs.

3. Drawing S13 of 23: Pier 2 Details:

Clarification:

A) Plan view 1/S13: The sixteen (16) longitudinal piles' orientation is to be in the bridge direction, not perpendicular to the pile cap.

B) Elevation view 2/S13: pile embedment up into cap to be 500, not 400.

A signed copy of this addendum sheet must be included with your bid submission for this project.

Signature of Contractor