

<b>PROJECT</b> QEH New AHU	<b>PROJECT NO.</b> 19-175
<b>DESCRIPTION</b> Addendum No. 2	<b>DATE</b> December 11, 2019

**Item No. 1 Reference Drawing M-1**

- .1 Clarification – Reference Air Handling Unit Schedule:
  - .1 Delete reference to starter. VFD only section is required.
  - .2 Unit to be provided with integral disconnect switch for each VFD. One VFD required per fan.

**Item No. 2 Reference Drawing M-2**

- .1 Clarification – Reference Paragraph 2.1.5.2:
  - .1 Provide hinged double-wall access doors with removable access panels on the other side for the supply fan, return fan, and filter section.
  - .2 Provide factory installed thermal pane reinforced glass viewports on supply and return fan access doors.
  - .3 Provide factory installed marine light for supply fan, return fan, and filter sections.

