



Transportation, Infrastructure,  
and Energy

PO Box 2000  
Charlottetown  
Prince Edward Island  
Canada C1A 7N8

Tel 902 368 5180  
Fax 902 368 5425  
[www.gov.pe.ca/](http://www.gov.pe.ca/)

## CAPITAL PROJECTS

### ADDENDUM NUMBER 2 for Route 2 – Milton Station/Springvale 2020 (Page 1 of 5)

---

TO: All Bidders

FROM: Mark Sherren, P.Eng.  
Western Regional Engineer

DATE: February 18, 2020

SUBJECT: Revisions

---

#### 1. SECTION 100 - GENERAL PROVISION

The 2020 PEITIE General Provisions and Contract Specifications for Highway Construction is now available online at:

[https://www.princeedwardisland.ca/sites/default/files/publications/highwayconstructionspecs\\_0.pdf](https://www.princeedwardisland.ca/sites/default/files/publications/highwayconstructionspecs_0.pdf)

#### 2. Replace Section 501 – ASPHALT CEMENT with the following:

##### 5) SECTION 501 - ASPHALT CEMENT

###### (Item 50109 - Surcharge for Polymer Liquid Asphalt)

Performance Graded Asphalt Cement (PGAC) on this contract shall comply with AASHTO M332 for the surface mix and shall be graded as PG 58-28H. Additionally the PGAC shall meet the elastic recovery requirements detailed in Appendix X1 of AASHTO M332. Note, when ordering the PGAC to include reference to the specification, grade with designation and the appendix (e.g., M332, PG 58-28H, Appendix X1).

The unit bid price for the above listed item shall be full compensation **for the additional cost of the purchase**, supply, haul, storage, and use of this product **over and above the cost of PG 58-28S**. No additional compensation shall be provided.

ADDENDUM NUMBER 2 (continued)  
for  
Route 2 – Milton Station/Springvale 2020  
(Page 2 of 5)

3. Replace 3 pages of Schedule C dated January 30, 2020 with the attached 3 pages dated February 19, 2020. This reflect a change in quantity for Item 50109 from 480 tonnes to 235 tonnes.

A signed copy of this addendum must be included with your bid submission on this project.

---

Signature of Contractor

## Schedule C

schedule of item for tender

Item Description and Price			Estimated Quantity	Contractor Total Price
<b>ASPHALT CEMENT</b>				
Section: 501	Item: 50101	Major Item		
			PER Tonnes	
			PER Tonnes	480.00 \$
			100	
<b>SURCHARGE FOR POLYMER LIQUID ASPHALT</b>				
Section: 501	Item: 50109			
			PER Tonnes	
			PER Tonnes	235.00 \$
			100	
<b>TACK COAT</b>				
Section: 601	Item: 60101			
			PER Square Metre	
			PER M2	68,000.00 \$
			100	
<b>ASPHALT LEVELLING : A</b>				
Section: 603	Item: 60326	Major Item		
			PER Tonnes	
			PER Tonnes	4,500.00 \$
			100	
<b>ASPHALT SEAL: B</b>				
Section: 603	Item: 60350	Major Item		
			PER Tonnes	
			PER Tonnes	3,700.00 \$
			100	
<b>HMA DRIVEWAY MIX</b>				
Section: 610	Item: 61003			
			PER Tonnes	
			PER Tonnes	100.00 \$
			100	

Total Carried Forward \$

From Previous Page

Total Carried Forward \$

## Schedule C

schedule of item for tender

Item Description and Price		Estimated Quantity	Contractor Total Price
<b>COLD PLANE CONST. JOINT</b>			
Section: 705	Item: 70501		
		PER Square Metr	
		PER M2	100.00 \$
		100	
<b>RAP: SHOULDER MATERIAL</b>			
Section: 712	Item: 71201		
		PER Square Metr	
		PER M2	16,700.00 \$
		100	
<b>COLD PLANE AND STOCKPILE</b>			
Section: 716	Item: 71601		
		PER Square Metr	
		PER M2	16,700.00 \$
		100	
<b>SIGNALLERS</b>			
Section: 901	Item: 90101		
		PER hrs	
Nineteen Dollars and 78 Cents		PER hrs	600.00 \$
		100	11,868.00
<b>FLEXBEAM GUIDERAIL: REMOVA</b>			
Section: 902	Item: 90201		
		PER Metres	
		PER M	440.00 \$
		100	
<b>FLEXBEAM GUIDERAIL: ERECT</b>			
Section: 903	Item: 90301		
		PER Metres	
		PER M	440.00 \$
		100	
Total Carried Forward \$			
From Previous Page			
Total Carried Forward \$			

## Schedule C

schedule of item for tender

Item Description and Price		Estimated Quantity	Contractor Total Price
<b>PAVEMENT EDGE DELINEATOR</b>			
Section: 904	Item: 90401		
		PER unit	
		PER unit	80.00 \$
		100	
<b>TEMPORARY MARKING</b>			
Section: 905	Item: 90501		
		PER Metres	
		PER M	60.00 \$
		100	
<b>RAISED TEMPORARY MARKING</b>			
Section: 905	Item: 90502		
		PER unit	
		PER unit	100.00 \$
		100	
<b>TRAFFIC CONTROL PLAN</b>			
Section: 908	Item: 90802		
		PER hrs	
Twenty-Five Dollars and 00 Cents		25.00 PER hrs	60.00 \$
		100	1,500.00
<b>GUIDERAIL END TREATMENT: SUPPLY &amp; INST.</b>			
Section: 909	Item: 90902		
		PER unit	
		PER unit	2.00 \$
		100	

Total Carried Forward \$ \_\_\_\_\_  
 From Previous Page

Total Carried Forward \$ \_\_\_\_\_

HST \$ \_\_\_\_\_

Grand Total \$ \_\_\_\_\_