



Transportation, Infrastructure,
and Energy

PO Box 2000
Charlottetown
Prince Edward Island
Canada C1A 7N8

Tel 902 368 5100
Fax 902 368 5425
www.gov.pe.ca/

CAPITAL PROJECTS

ADDENDUM NUMBER 1 for Gunns Bridge Structure Replacement (Page 1 of 1)

TO: All Bidders

FROM: Neil Lawless, P.Eng.
Bridge Engineer

DATE: February 25, 2020

SUBJECT: Revisions
Errata to Schedule A

1. Drawing S1 of 10: General Notes - Steel Notes numbers 1, 2, and 3:

Delete: 610 G/SQM as per CSA G164.

Insert: 720 G/SQM as per ASTM A123/ A123M.

2. Schedule A: Bid Item #130160 - Traffic Barrier:

First paragraph, last sentence:

Delete: 610 g/ sq m as per CSA G164.

Insert: 720 g/ sq m as per ASTM A123/ A123M.

3. Schedule A: Item #1: GENERAL PROVISIONS AND CONTRACT SPECIFICATIONS for HIGHWAY CONSTRUCTION

The 2020 PEITIE General Provisions and Contract Specifications for Highway Construction is now available online at:

https://www.princeedwardisland.ca/sites/default/files/publications/highwayconstructionspecs_0.pdf

4. DRAWING S4: Plan new

Clarification: The quantity of piles at the pier is six (6), not seven (7). Refer also to S8

5. Schedule A: Bid Item #110112 - Cast-in-Place Concrete:

Second last paragraph regarding galvanizing :

Delete: 610 g/ sq m as per CSA G164.

Insert: 720 g/ sq m as per ASTM A123/ A123M.

Last paragraph regarding Sealer:

Approved alternate sealer: Pentreat 244-100.

A signed copy of this addendum must be included with your bid submission on this project.

Signature of Contractor